# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
## Office of the Executive Engineer, Dasarahalli Division.

DTS COPY

NAME OF WORK: Improvements & construction of culverts and Damaged Covering slab in Dasarahalli ward No 15

| Sl. No | Description of work | Unit | Qty | Rate to be Quoted | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications. | Cum | 39.53 | | |
| 2 | Plain cement concrete M10 MIx with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications. | Cum | 19.76 | | |
| 3 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for beams, columns, staircase and roof with M-20(Cement-320 kg/cum) complete as per specifications. | Cum | 13.18 | | |
| 4 | Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications. | Sqm | 197.64 | | |
| 5 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications. | Cum | 39.53 | | |

Number of Corrections:

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

**DTS Approved**